

#### 2012-2013 Major Upgrade





Stage I Upgrade (4500 meter ops) - completed in 2013

- •New personnel sphere (rated to 6500 meters)
- •New electrical/optical penetrators
- •New syntactic foam
- •New command and control system
- •Upgraded frame to support new sphere
- •Upgraded life support system
- •Minor modifications to remaining SOC systems













#### 2020-2021 Overhaul Objectives

Stage II - completion Sept 2021


• Final 6,500m syntactic integration

New MB & VB H.P. Air Spheres

- New VB system
- New VB seawater pump
- New 10 H.P. thrusters
- New motor controllers
- New hydraulic plant

6500m syntactic blocks

Ballast spheres



Motor controllers

Dual hydraulic plants

**VB** water pump



















Frame arrives!






























































Syntactic fit-up

















Assembly in-progress















New VB spheres and J-boxes installed














#### Imaging system upgrades

- New DSPL 4K cameras
- New Pan & Tilt Units
- 4 wide-angle DSPL Flex-link cameras
- Improved positioning of cameras
- Improved lighting positioning/separation
- Improved still cameras imaging
- Proxy videos created real-time in-hull
- Improved observer monitors
- Improved camera controllers

#### Data system upgrades

- Upgrade to Navigation (NAV-G 3.0)
- 'SEALOG' event logger
- Improved meta data display (tablets)
- New temperature suite (LoT, HiT, Heat Flow)















# Return to dive operations 2021 - 2022 Operations Schedule

- Jul Aug '21 Dockside Testing
- Sep Oct '21 Sea-trials & 6500m Certification
- Oct '21 Science Verification Expedition
- Oct Nov '21 Craig Young Larval Seeps
- Nov Dec '21 Dave Valentine GOM
- Jan Feb '22 Shawn Arellano 9N EPR
- TBD Dan Fornari 9N EPR
- TBD Lisa Levin San DIego
- TBD San Diego Basin
- TBD Chris German Deep water vents

















#### **THANK YOU!**

NDS FACILITY







