


# R/V SIKULIAQ: Load Handling System (LHS) FIC Update June 2012




Marc Willis, OSU-COAS  
Marine Science Technical Director  
SIKULIAQ Shipyard Project Office




# SIKULIAQ Load Handling System

The Load Handling System consists of:

- Overboarding boom
- Capable winches
- “Smart” control system
- Sensors are key
  - Proximity sensors in docking head
  - Tension sensors on wire
  - Motion sensors on ship
- **Proximity sensors** provide feedback for Auto-position mode
- **Tension sensors** provide feedback for Render/Recover mode and Auto-Position
- **Motion sensors** provide feedback for Motion compensation mode
- **Control software** glues all the parts together – the real “smarts”




The overboarding boom is the “dumbest” part of the system – the magic is in the winches and control system




*Winch Control Room*

*Forward Winch Room*  
 • Both winches can be rotated to serve either A-Frame/crane or LHS



## Outboard and Inboard Profiles


# LHS Sensor Arrangement



**Control Software** integrates sensors and winch/boom controls


# LHS Boom



- Boom is patterned on the “Overhead Crane” concept in the NSF/ONR Load Handling Workshop Report.
- LHS Boom is located in the overhead of Baltic Room (02 level)
- Exits through side shell door
- Controlled locally and from Winch Control Room
- Overboards either Hydro and CTD Winch



Side Shell “Baltic” Door


Winch Control Room





# LHS Operating Positions

# Major Components



**Removable  
Docking Head**

-Replacement docking heads for other equipment can be attached

**Telescoping Boom**

**Base Carriage**

- carries inboard sheave and lowering cylinders  
- Moves boom inside Baltic Room.

# LHS Docking Head


Damping  
Cylinders  
-Adjustable by  
operator

Guide Rollers

Docking Collar

-Bolt-on, will be replaced  
with custom bumper for  
trials.

Bolting Plate





# LHS Docking Head

## Docking Collar

-Bolt-on, will be replaced with custom bumper for trials.

## Guide Rollers

## Damping Cylinders

-Adjustable by operator



# LHS Boom under construction



# Factory Testing, March 2012

- Testing was conducted at Rapp-Hydema NW, Seattle
- LHS boom was upside down for testing – not practical to test in normal orientation
- Full load and motion tests were performed using a crane to supply load
- Test was satisfactorily completed
- LHS is now at the shipyard, and will be installed in the Baltic Room module within the next few weeks.



# Factory Testing, March 2012





For further information:

Marc Willis  
OSU-COAS  
SIKULIAQ Shipyard Project  
Office  
willis@coas.oregonstate.edu  
715-735-0372

Moving load test, March 2012