

Performance Metrics Planning and Management


Robert Paulos

University of Wisconsin – Madison

IceCube Project

May 4 - 7, 2010

NSF Large Facilities Workshop




Topics

*NSF Large
Facilities
Workshop*

May 4-7, 2010

- IceCube Context
- Performance Metric Planning
- Project Performance – EV and Financial
- A Few Subsystem Specific Examples




About IceCube

*NSF Large
Facilities
Workshop*

May 4-7, 2010

- IceCube is a \$275M collaborative project - build a neutrino telescope at the South Pole
- Involves 34 institutions worldwide - UW is the lead (host lab)
- Funding
 - \$242M from NSF
 - Non-US institutions are self-funded and make up the balance (>\$30M)



Basic Elements of IceCube


*NSF Large
Facilities
Workshop*


May 4-7, 2010



- Hot Water Drill
 - Drills holes in ice sheet 2.5 km deep and 60 cm in diameter
 - Uses hot water (~190F) at high pressure (~1000psi)
- Instrumentation
 - Deployed in holes on cable in regular array
 - 5000 optical modules with self-contained digitizing electronics
- Software and computing
 - Dedicated lab at SP for data filtering and storage
 - Software development for reconstruction of events and simulation


Amundsen-Scott South Pole Station






Performance Metrics – Observations

*NSF Large
Facilities
Workshop*
May 4-7, 2010



- In general, project personnel don't like them – work through this and show they add value
- Earned value metrics part of the culture now – not everyone will be convinced of their value
- Good metrics work as a valuable tool at many levels to assess progress against plans
- Data should be easy to collect and understand – simple is better (of course not always the case)




Performance Metric Planning

*NSF Large
Facilities
Workshop*

May 4-7, 2010

- Important to develop metrics from the bottom up – this approach will ensure buy-in, usefulness/meaning
- Metrics (key performance indicators) are traceable to one or more project goals
- Objective, quantifiable metrics are preferred over subjective measures
- Should be easy to understand
- Easy to collect data in a timely manner
- Simple metrics are best, e.g. electronics boards ready for shipment




Performance Metrics Planning (cont.)

*NSF Large
Facilities
Workshop*

May 4-7, 2010

- IceCube project office worked with each L2 and L3 manager to develop and report on metrics in their area of responsibility
- During construction execution phase reporting on metrics occurred at monthly status meetings
 - Initial metrics were refined in this forum
 - Metrics included EV, milestone progress, and unique measures appropriate to subsystem
 - Project controls can help by providing basic EV data by WBS
 - Milestone progress was subjective, could have been less so



Metrics from IceCube

NSF Large
Facilities
Workshop
May 4-7, 2010

- Earned Value related metrics and reporting
 - CSSR
 - S-Curve
 - Cost Baseline
 - Variance report
 - Contingency status


IceCube Project CSSR

IceCube Neutrino Observatory Cost Schedule Status Report Reporting Period Ending: 2/28/2006 ¹											
OBS Structure L2	Cumulative To Date (AY K\$)					At Completion (AY K\$)			Complete (%)		
	Budgeted Cost ²		Actual Cost of Work Performed	Variance		Budgeted AY \$s	Latest Revised Estimate	Variance	Scheduled	Performed	Actual
	Work Scheduled	Work Performed		Schedule	Cost						
PROJECT SUPPORT	17169.4	17174.4	17278.8	5.0	-104.4	29904.8	30009.2	-104.4	57.4%	57.4%	57.8%
IMPLEMENTATION	21312.5	20990.6	21103.1	-321.9	-112.6	32388.6	32501.2	-112.6	65.8%	64.8%	65.2%
INSTRUMENTATION	38185.2	38267.1	38052.2	81.9	214.9	65432.7	65217.8	214.9	58.4%	58.5%	58.2%
DATA ACQUISITION	22299.8	22151.5	22467.6	-148.3	-316.1	32864.6	33180.7	-316.1	67.9%	67.4%	68.4%
DATA SYSTEMS	12483.3	11771.9	12169.9	-711.4	-398.0	25017.6	25415.6	-398.0	49.9%	47.1%	48.6%
DETECTOR COMM. & VERIFICATION	9605.8	9283.4	8929.6	-322.4	353.8	18825.0	18471.2	353.8	51.0%	49.3%	47.4%
RPSC SUPPORT	16189.7	11345.5	8087.3	-4844.2	3258.1	32022.1	28764.0	3258.1	50.6%	35.4%	25.3%
NSF	545.4	545.4	545.4	0.0	0.0	1263.0	1263.0	0.0	43.2%	43.2%	43.2%
Sub Total	137791.1	131529.7	128633.9	-6261.4	2895.8	237718.5	234822.8	2895.8	58.0%	55.3%	54.1%
Management Reserve											
Total Contingency Items Outside of Approved Baseline						35,334.8	38,230.6	2,895.8			
IceCube Neutrino Observatory ²	137,791.1	131,529.7	128,633.9	-6,261.4	2,895.8	273,053.3	273,053.3	0.0	58.0%	55.3%	54.1%

Notes: 1 Incorporates approved and currently pending baseline changes.

2 Total Budget at Completion includes non-US contributions \$1,283K over the amount in the post Hartill III baseline.


3 The budgeted contingency is: 33.3% of the Budgeted cost of work remaining.



S-Curve

NSF Large
Facilities
Workshop

May 4-7, 2010



Cost Baseline

	<u>Baseline (Hartill 02/04)</u>	<u>Current (Hartill 05/09)</u>
Cost: TPC	\$271.8 million	\$275.3 million
NSF	\$242.1 million	\$242.1 million
Non-US	\$ 29.7 million	\$ 33.2 million

Earned Value: \$241.6 million (90.1%)


Contingency (Cont. % of Remaining Work):
\$ 40 million (23%) \$ 7 million (26.4%)

Most Technical Risk Retired

**Completion
Schedule:**

4th Quarter, 2010

2nd Quarter, 2011



Variations at the end of PY7

*NSF Large
Facilities
Workshop*

May 4-7, 2010




Schedule Variance is \$385K

- This favorable variance is due to RPSC's FY2008 performance.

Cost Variance is \$1,758K


- Implementation \$498K: This variance is related to the summer training under-run, and senior engineers ramping down ahead of schedule.
- RPSC \$992K: Favorable FY08 labor rate
- Pre Operations \$172K: Mostly lagging invoices for Computing H/W.
- Instrumentation -\$182K: DOM Production has been resumed in PSL, with the purchase of Materials and Equipments ahead of Schedule.




Contingency Status

NSF Large
Facilities
Workshop

May 4-7, 2010






Metrics from IceCube

*NSF Large
Facilities
Workshop*

May 4-7, 2010

- Quantitative metrics that measure technical performance
 - String installation
 - Drill performance
 - Instrumentation production
 - Integration, test, yield




String and IceTop Installation

Strings (<i>Actual & Plan</i>)	<i>04/05</i>	<i>05/06</i>	<i>06/07</i>	<i>07/08</i>	<i>08/09</i>	<i>09/10</i>	<i>10/11</i>
Annual Baseline	1	8	13	18	19[†]	18[†]	9
Cumulative	1	9	22	40	59	77	86
†Deep Core (<i>Actual & Plan</i>)					1	5	
†Cumulative					1	6	
IceTop Stations (<i>Actual/Plan</i>)	<i>04/05</i>	<i>05/06</i>	<i>06/07</i>	<i>07/08</i>	<i>08/09</i>	<i>09/10</i>	<i>10/11</i>
Annual Baseline	4	12	10	14	19	14	7
Cumulative	4	16	26	40	59	73	80




String Installation Status and Plans


1 + 8 + 13 + 18 + 19 + 20 =
79 strings
 to date





AMANDA vs. IceCube Drilling






Instrumentation Production




Instrumentation Production CY2004 - CY2008 for 80 strings installed





10" PMT Hamamatsu



Flasher board

Main board


33cm



IceCube Digital Optical Module (DOM)

DOM integration 2006


IceCube DOM Integration PY5 (April, 2006 to March, 2007) - Plan vs. Actual




DOM integration 2006 by production site


DOM Production Site *Integration* Status - PY5 (April, 2006 - March, 2007)

Week ending 9/23/06





DOM test by prod site – CY2006



Final Acceptance Test Yield - 2006

Ship Yield and First Pass Yield - CY2006

